

## **General Disclaimer**

### **One or more of the Following Statements may affect this Document**

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some of the material. However, it is the best reproduction available from the original submission.

DOE/NASA CONTRACTOR  
REPORT

DOE/NASA CR-150859

DESIGN AND INSTALLATION PACKAGE FOR SOLAR HOT  
WATER SYSTEM

Prepared from documents furnished by

Solar Engineering and Manufacturing Company  
1091 Southwest 1st Way  
Deerfield Beach, FL 33441

Under Contract NAS8-32248 with

National Aeronautics and Space Administration  
George C. Marshall Space Flight Center, Alabama 35812

For the U.S. Department of Energy

(NASA-CR-150859) DESIGN AND INSTALLATION  
PACKAGE FOR SOLAR HOT WATER SYSTEM (Solar  
Engineering and Mfg. Co.) 32 p HC A03/MF  
A01 CSCL 10A

G3/44



**U.S. Department of Energy**



**Solar Energy**

## TABLE OF CONTENTS

System Performance Specification	1
Acceptance Data Package	11
Hazard Analysis	15
Installation Manual	16

~~REPRODUCED~~ PAGE BLANK NOT FILMED

SEMCO  
SYSTEM PERFORMANCE SPECIFICATIONS

SHC-3021

1.0 Introduction

This System Performance Specification establishes the requirements for the design and performance of the solar powered Domestic Hot Water (DHW) System to be delivered by the system contractor. It designated the Interim Performance Criteria (IPC) applicable to the above system and defines any anticipated deviations. The appendices specify the performance for the Site #1 system and subsystems and Site #2 system and subsystems together with installation drawings for both sites.

2.0 Applicable Documents

This section lists the Government and Contractor reference Documents Applicable to the System Performance Specification and the appendices attached hereto.

2.10 Government Documents

2.11 Interim Performance Criteria for Solar Heating and Combined Heating/Cooling Systems and dwellings, January 1, 1975 published by the U. S. Department of Housing and Urban Development (HUD).

2.12 Solar Heating and Cooling Development Program Request for Proposal No. AP32-75-406 by the National Aeronautics and Space Administration dated October 17, 1975.

2.13 Contract document NAS8-32248 between National Aeronautics and Space Administration (NASA) and Solar Engineering & Manufacturing Co. (SEMCO, ten pages with Appendices A through G, dated October 28, 1976.

2.20 System Contractor Documents

2.21 Response to Request for Proposal AP32-75-405 by the Solar Engineering & Manufacturing Co. (SEMCO) dated March 5, 1976.

2.22 Collector Performance Test Report from Florida Solar Energy Center for Model FP 40-3 submitted in the March monthly report and for Model FP 40-4 (1" insulation) recently submitted to FSEC for further testing. Second Performance Test. Report currently pending.

2.23 Required Documentation for Prototype Design Review submitted May 2, 1977.

2.24 Site Data Acquisition System instrumentation design submitted on April 22, 1977 and revised on May 25, 1977.

2.25 Various documents submitted with this System Perform-

ance Specification as part of the May report as follows:

- 2.251 List of Materials to be Delivered
- 2.252 Testing of Materials to be Delivered
- 2.253 Testing of Installed Systems
- 2.254 Installation, Operation and Maintenance Manual
- 2.255 Design Data Brochure
- 2.256 Training Program

3.0 Application of IPC by Type of System

The application of each paragraph of the Interim Performance Criteria (IPC) to each system is provided in the following table.

TABLE I

Residential Systems, Interim Performance Criteria Summary

Following 6 Pages



TABLE I

SPECIFICATION NO. \_\_\_\_\_

REVISION \_\_\_\_\_

DATE \_\_\_\_\_

## RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY

SHEET 1 OF 6

APPLICATION

A - APPLICABLE TO SYSTEMS INDICATED  
 I - APPLICABLE TO SYSTEM AND BUILDING  
 NA - NOT APPLICABLE

TYPE SYSTEMS

H - HEATING  
 HC - HEATING AND COOLING  
 HW - HOT WATER

RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS			RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS		
	H	HC	HW		H	HC	HW
1.1 H and HC System Performance	A	A	A	1.3.1 Collector Efficiency	A	A	A
1.1.1 Heating Design Temperatures	I	I	NA	1.4 Thermal Storage	A	A	A
1.1.2 Cooling Design Temperatures	NA	I	NA	1.4.1 Storage Capacity and Rate	A	A	A
1.1.3 Relative Humid- ity and Water Vapor Pressure	I	I	NA	1.5 Habitability of Occupied Spaces	A	A	A
1.1.4 Solar Contribution	A	A	A	1.5.1 Heat or Humidity Transfer Effects	I	I	I
1.1.5 Operation Impairment	A	A	A	1.6 Energy Transport Efficiency	A	A	A
1.2 HW System Subsystem Performance	A	A	A	1.6.1 Thermal Losses and Electrical Power	A	A	A
1.2.1 Water Design Temperature	I	I	I	1.7 Control	A	A	A
1.2.2 Storage Design Capacity	A	A	A	1.7.1 Installation and Maintenance	A	A	A
1.2.3 Solar Contribution	A	A	A	1.7.2 Manual Adjustment	A	A	A
1.2.4 Operational Impairment	A	A	A	1.7.3 Inhabited Space Temperature	A	A	NA
1.3 Collector Performance	A	A	A	1.7.4 Hot Water Temperature	A	A	A
				1.8 Auxiliary Energy	A	A	A
				1.8.1 Design Loads	A	A	A

ORIGINAL PAGE IS  
 OF POOR QUALITY

TABLE I  
CONTINUATION SHEET

SPECIFICATION NO. \_\_\_\_\_  
REVISION \_\_\_\_\_  
DATE \_\_\_\_\_

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY

SHEET 2 OF 6

RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS			RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS		
	H	HC	HW		H	HC	HW
2.1 System Design Conditions	A	A	A	2.3.2 Pressure Test: Potable Water	A	A	A
2.1.1 Equipment Capabilities	A	A	A	2.3.3 Air Transport Systems	A	A	A
2.1.2 Noise or Erosion-Corrosion	A	A	A	2.4 Collector Adjustment	A	A	A
2.1.3 Operating Conditions	A	A	A	2.4.1 Orientation and Tilt	A	A	A
2.1.4 Fluid Flow in Collectors	A	A	A	2.4.2 Mutual Shadowing	A	A	A
2.1.5 Entrapped Air	A	A	A	2.5 Subsystem Isolation	A	A	A
2.1.6 Thermal Expansion of Fluids	A	A	A	2.5.1 Shutdown in Multi-family Housing	A	A	A
2.1.7 Pressure Drops	A	A	A	2.6 Heat Transfer Fluid Quality	A	A	A
2.1.8 Condensate Removal	NA	A	NA	2.6.1 Liquid Quality	A	A	A
2.2 Mechanical Stresses	A	A	A	2.6.2 Air Quality	A	A	A
2.2.1 Vibration Stress Levels	A	A	A	2.6.3 Fluid Quality	A	A	A
2.2.2 Vibration from Moving Parts	A	A	A	2.6.4 Freezing Protection	A	A	A
2.2.3 Water Hammer	A	A	A	2.7 Piping Supports	A	A	A
2.2.4 Vacuum Relief Protection	A	A	A	2.7.1 Applicable Plumbing Standards	A	A	A
2.2.5 Thermal Changes	A	A	A	2.8 Excessive Pressure and Temperature Protection	A	A	A
2.2.6 Flexible Joints	A	A	A	2.8.1 Relief Valves and Vents	A	A	A
2.3 Leakage Prevention	A	A	A	3.1 Structural Design Basis	A	A	A
2.3.1 Pressure Test: Nonpotable Fluids	A	A	A	3.1.1 Applicable Standards	A	A	A

ORIGINAL PAGE IS  
OF POOR QUALITY

ORIGINAL PAGE IS  
OF POOR QUALITY

TABLE 1  
CONTINUATION SHEET

SPECIFICATION NO. \_\_\_\_\_  
REVISION \_\_\_\_\_  
DATE \_\_\_\_\_

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY

RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS			RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS		
	H	HC	HW		H	HC	HW
3.1.2 Service Loads	A	A	A	3.8.2 Constrain Loads	A	A	A
3.2 Failure Loads and Load Capacity	A	A	A	3.9 Ponding Condition	A	A	A
3.2.1 Ultimate Load Combinations	A	A	A	3.9.1 Design Provisions	A	A	A
3.2.2 Ice Loads	A	A	A	4.1 Plumbing and Electrical Installation	A	A	A
3.2.3 Vehicular Loads	I	I	I	4.1.1 Plumbing Codes	A	A	A
3.2.4 Load Capacity	A	A	A	4.1.2 Electrical Codes	A	A	A
3.3 Damage Control	A	A	A	4.2 Fail-Safe Controls	A	A	A
3.3.1 Resistance to Damage	A	A	A	4.2.1 System Failure Prevention	A	A	A
3.3.2 Glazing Design	A	A	A	4.2.2 Automatic Pressure Relief Valves	A	A	A
3.4 Cyclic Loads	A	A	A	4.3 Fire Safety	A	A	A
3.4.1 Deflection Limitations	A	A	A	4.3.1 Applicable Fire Standards	A	A	A
3.5 Cutting of Structural Elements	I	I	I	4.3.2 Penetrations through Fire Rated Assemblies	I	I	I
3.5.1 Design Provisions	I	I	I	4.4 Toxic	A	A	A
3.6 Creep and Residual Deflection	I	I	I	4.4.1 Provisions of Catch Basins	A	A	A
3.6.1 Deflection Limitations	I	I	I	4.4.2 Detection of Toxic and Flammable Fluids	A	A	A
3.7 Hail Resistance	A	A	A	4.5 Safety	I	I	I
3.7.1 Hail Size and Loading	A	A	A	4.5.1 Emergency Egress and Access	I	I	I
3.8 Constraint Loads	A	A	A	4.5.2 Identification and Location of Controls	A	A	A
3.8.1 Foundation Settlement	A	A	A	4.6 Protection of Potable Water and Circulated Air	A	A	A



TABLE 1

REVISION \_\_\_\_\_

DATE \_\_\_\_\_

## RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY

SHEET 4 OF 6

APPLICATION

A - APPLICABLE TO SYSTEMS INDICATED.  
 I - APPLICABLE TO SYSTEM AND BUILDING  
 NA - NOT APPLICABLE

TYPE SYSTEMS

H - HEATING  
 HC - HEATING AND COOLING  
 HW - HOT WATER

RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS			RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS		
	H	HC	HW		H	HC	HW
4.6.1 Contamination by Materials	A	A	A	5.2.4 Leakage	A	A	A
4.6.2 Separation of Circulation Loops	A	A	A	5.2.5 Deterioration of Gaskets and Sealants	A	A	A
4.6.3 Backflow Prevention	A	A	A	5.2.6 Transmission Losses Due to Outgassing	A	A	A
4.6.4 Growth of Fungi	A	A	A	5.3 Chemical Compatibility of Components	A	A	A
4.7 Excessive Surface Temperatures	A	A	A	5.3.1 Materials/Transfer Fluid Compatibility	A	A	A
4.7.1 Protection from Heated Components	A	A	A	5.3.2 Corrosion of Dissimilar Materials	A	A	A
5.1 Effects of External Environment	A	A	A	5.3.3 Corrosion by Leachable Substance	A	A	A
5.1.1 Solar Degradation	A	A	A	5.3.4 Effects of Decom- position Products	A	A	A
5.1.2 Soil Corrosion	A	A	A	5.4 Components Involving Moving Parts	A	A	A
5.1.3 Airborne Pollutants	A	A	A	5.4.1 Wear and Fatigue	A	A	A
5.1.4 Dirt Retention on Cover Plate Surface	A	A	A	6.1 Accessibility for Maintenance	A	A	A
5.1.5 Abrasive Wear	A	A	A	6.1.1 Access for System Maintenance	A	A	A
5.1.6 Fluttering by Wind	A	A	A	6.1.2 Access for System Monitoring	A	A	A
5.2 Temperature and Pressure Resistance	A	A	A	6.1.3 Draining and Filling of Liquids	A	A	A
5.2.1 Thermal Degradation	A	A	A	6.1.4 Flushing of Liquids Subsystems	A	A	A
5.2.2 Deterioration of Heat Transfer Fluids	A	A	A	6.1.5 Filters	A	A	A
5.2.3 Thermal Cycling Stresses	A	A	A	6.1.6 Potable Water Shutoff	A	A	A

TABLE I

SPECIFICATION NO. \_\_\_\_\_

REVISION \_\_\_\_\_

DATE \_\_\_\_\_

## RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY

APPLICATION

A - APPLICABLE TO SYSTEMS INDICATED  
 I - APPLICABLE TO SYSTEM AND BUILDING  
 NA - NOT APPLICABLE

TYPE SYSTEMS

H - HEATING  
 HC - HEATING AND COOLING  
 HW - HOT WATER

RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS			RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS		
	H	HC	HW		H	HC	HW
6.2 Installation, Operation and Maintenance Manual	A	A	A	7.3.1 Space Use	I	I	I
6.2.1 Installation Instructions	A	A	A	7.3.2 Shading of Adjacent Structures	I	I	I
6.2.2 Maintenance and Operation Instructions	A	A	A	7.3.3 Impact on Environment	I	I	I
6.2.3 Maintenance Plan	A	A	A	7.3.4 View	I	I	I
6.2.4 Replacement Parts	A	A	A	8.1 Interference with Mechanical Operation	I	I	I
6.3 Repair and Service Personnel	A	A	A	8.1.1 Blockage of Solar Subsystem	I	I	I
6.3.1 Maintenance of H and HC Systems	A	A	A	8.1.2 Shading of Collector	I	I	I
6.3.2 Maintenance of DHW System	A	A	A	8.1.3 Sensor Location	I	I	I
7.1 Design	I	I	I	8.2 Mechanical and Electrical Functioning of Dwelling and Site	I	I	I
7.1.1 Dwelling Design	I	I	I	8.2.1 Exhaust and Venting	I	I	I
7.1.2 Mobile Home Design	I	I	I	8.2.2 Utilities	I	I	I
7.1.3 Site Design	I	I	I	8.3 Mechanical and Electrical Functioning of Connections	I	I	I
7.1.4 Passive Use of Solar Energy	I	I	I	8.3.1 Plumbing Connections	I	I	I
7.2 Adequate Space	I	I	I	8.3.2 Electrical Connections	I	I	I
7.2.1 Collector Area	I	I	I	9.1 Structural Integrity	I	I	I
7.2.2 Storage Area	I	I	I	9.1.1 Movement in Adjacent Structures	I	I	I
7.2.3 Utility Chases	I	I	I	9.2 Structural Integrity of Dwelling	I	I	I
7.3 Functioning of Dwelling Site	I	I	I				

ORIGINAL PAGE IS  
OF POOR QUALITY

TABLE I  
CONTINUATION SHEET

SPECIFICATION NO. \_\_\_\_\_  
REVISION \_\_\_\_\_  
DATE \_\_\_\_\_

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY

SHEET 6 OF 6

RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS			RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEMS		
	H	HC	HW		H	HC	HW
9.2.1 Loads	I	I	I	11.3.1 Material Compatibility	A	A	A
9.2.2 Penetration of Structural Members	I	I	I	12.1 Maintainability of M, HC, HW Systems	I	I	I
9.3 Structural Connections	I	I	I	12.1.1 Accessibility	I	I	I
9.3.1 Structural Connections	I	I	I	12.1.2 Misuse	I	I	I
9.3.2 Brittle Sub- system	I	I	I	12.1.3 Permanent Mainte- nance Accessories	I	I	I
9.3.3 Strength and Stiffness	I	I	I	12.2 Maintainability of Dwelling and Site	I	I	I
10.1 Safety of Dwelling and Site	I	I	I	12.2.1 Accessibility	I	I	I
10.1.1 Fire	I	I	I	12.2.2 Ice Damage	I	I	I
10.1.2 Accidents	I	I	I	12.3 Connections	I	I	I
11.1 Durability	I	I	I	12.3.1 Accessibility	I	I	I
11.1.1 Vegetation	I	I	I	13.1 Visual Character- istics of Dwelling and Site	I	I	I
11.2 Durability and Reliability of Dwelling and Site	I	I	I	13.1.1 Dwelling	I	I	I
11.2.1 Chemical Corrosion	A	A	A	13.1.2 Neighborhood	I	I	I
11.2.2 Heat and Moisture	I	I	I				
11.2.3 Exterior Penetrations	I	I	I				
11.3 Durability and Reliability of Connections	A	A	A				

ORIGINAL PAGE IS  
POOR QUALITY

4.0 Deviation From Interim Performance Criteria

None

5.0 Government Furnished Property

5.1 Site Data Acquisition System supplied and installed by IBM.

5.2 Instrumentation equipment including thermowells, sensors, wiring and J-Box supplied by IBM and installed by system contractors.

6.0 Government Directed Requirements

See Contract NAS8-32248

7.0 Geographical Area

7.1 Operational Test Site #1. The Contract Domestic Hot Water (DHW) System is for a single family residence located in the Loxahatchee Wildlife Refuge, Palm Beach County, west of Boynton Beach, near Ft. Lauderdale, Florida. Operating altitude is approximately 20 feet above sea level.

7.2 Operations Test Site #2. The Contract Domestic Hot Water (DHW) System is for a single family residence located at a Public Housing Project, 1777 Wren Ave., Macon, Georgia. Operating altitude is approximately 500 feet above sea level.

8.0 System Appendices

Appendix A Domestic Hot Water System  
Operational Test Site #1  
Loxahatchee Wildlife Refuge  
Single Family Residence  
Model - Semco DHW 2/120 DF

Appendix B Domestic Hot Water System  
Operational Test Site #2  
Macon, Georgia  
Single Family Residence  
Model - Semco DHW 2/120 DWHE

ORIGINAL PAGE IS  
OF POOR QUALITY



## APPENDIX A

### Operational Site #1 - Loxahatchee Wildlife Refuge

#### Hot Water

75 gallons of potable hot water shall be delivered at no less than 3 gal/min at temperatures no less than 140°F. Recovery time shall be no greater than 8 hrs. The average hot water heating load will be 1,125,000 BTU/Month of which 10% is provided by auxiliary energy.

$$(75 \times 8.33 \times (140-80) \times 30 = 1,125,000 \text{ BTU})$$

#### Operating Requirements

The maximum electrical energy required to drive the solar portion of the system at its rated capacity shall be no greater than 0.10 KW/hr. The maximum electrical energy required to drive the complete system shall be no greater than 4.6 KW/hr. The average yearly electrical energy required to drive the system shall be no greater than 688 K.W/yr.

$$(112,500 \div 3,412 \times 12 = 396 \text{ KW/yr}) \text{ plus} \\ (0.10 \times 8 \times 365 = 292 \text{ KW/yr}) = 688 \text{ KW/yr}$$

#### Physical Data

<u>Subsystem</u>	<u>Design Life</u> no less than	<u>Weight (Filled)</u> no greater than	<u>Installation</u> <u>dimension</u>
Storage	5 yrs	1,200 lbs	120 gal
Potable Water	-	1,000 lbs	-
Aux - E	5 yrs	-	4.5 K.W.
Collector	20 yrs	180 lbs	4' x 10'
Controller	5 yrs	3 lbs	3" x 4" x 6"
Pump	5 yrs	10 lbs	1/20 H.P
Transport	5 yrs	1 lb/ft	-



## ACCEPTANCE DATA PACKAGE

ORIGINAL PAGE IS  
OF POOR QUALITY

### 1.0 INTRODUCTIONS

The following report is a description of the test site residential solar water heating systems installed and modified by SEMCO. The list of materials and schematics are for the "as is" configuration. No further modifications are anticipated. This data is prepared and presented in anticipation of the "Operational Test Review", scheduled for November 9, 1978 at the Macon, Georgia site.

### 2.0 MATERIAL LIST

- 2.1 COLLECTORS - Semco Flat Plate - two (2) supplied  
Model 40-7 - Double Glazed With Tempered Glass  
Total area of 80 sq. ft.
- 2.2 STORAGE TANKS - State Ind - 120 Gallon tank  
Macon Site - Double wall heat exchanger using a Roll-Bond copper pannel wrapped around the lower portion of the steel tank with graphite filled polybutaline mastic between the tank and Roll-Bond pannel.  
Loxahatchee Site - Standard direct feed solar tank.  
Both tanks have a 4,500 watt electric booster element.
- 2.3 CIRCULATING PUMPS - Grundfos - Hot Water  
Macon Site UP 26-64 F 1/12 H.P.  
Loxahatchee Site UP 20-42 F 1/20 H.F.
- 2.4 DIFFERENTIAL CONTROLLER Hawthorne Ind.  
Variflo Proportional Control Model H-1510
- 2.5 TRANSPORT FLUID  
Macon Site has silicone oil transport fluid by Dow Corning Q2-1132 in a closed loop flowing between the collectors and the heat exchanger.  
Loxahatchee Site has water as the transport fluid in a direct feed system.
- 2.6 SAFETY FEATURES  
Both sites have a Pressure/temperature relief valve at the top of the transport fluid loop and a mixing valve in the hot water to house line.  
Macon Site has a Diaphram Expansion tank in the fluid transport loop.  
Loxahatchee Site has a vacuum breaker at the top of the transport fluid loop and an air bleeder valve at the top


of the storage tank. These devices were required because of the weekly shut down of the private water system at the Loxahatchee site which drained water from the fluid transport loop and introduced air into the fluid transport loop which eventually found its way to the top of the storage tank causing splattering when the hot water was first turned on.

2.7 FLUID TRANSPORT TUBE 1/2" copper tube insulated with 5/8 Dia. x 3/8 wall armflex pipe insulation assembled with standard sweat copper fittings and valves.

ORIGINAL PAGE IS  
OF POOR QUALITY


SEMCO, MACON, GA

TOTAL RADIATION



120 GALLON SOLAR WATER HEATER  
DOUBLE WALL HEAT EXCHANGER  
PUBLIC HOUSING PROJECT  
1777 WREN AVE  
MACON, GEORGIA  
OFF EISENHOWER PARKWAY

PAGE



120 GALLON SOLAR WATER HEATER  
LOXAHATCHEE NATIONAL WILD LIFE REFUGE  
PALM BEACH COUNTY, FLORIDA  
WEST OF LANTANA/BOYNTON



**ORIGINAL PAGE IS  
OF POOR QUALITY**

HAZARD ANALYSIS

There are only two major system hazards that require attention. The first is that of hurricane winds blowing the collectors off the roof and causing damage to adjacent property. This problem has been overcome by anchoring each collector to the roof at four separate points and having the anchoring procedure designed and certified by a Professional Engineer. This has been done for the subject contract. The second hazard consideration is that of static loading and pressure build up in the collector. This problem has been overcome by installing a Temperature-Pressure relief valve at the upper collector hot water outlet with a blow off line leading down to within 4 to 6 in. of the roof surface. This safety feature has been designed into the system.



## INSTALLATION

### TABLE OF CONTENTS

Installation, Operation and Maintenance Mannual	Page
SEMCO Solar Water Heater Installation Procedure	17
Collector Installation	17
Transport Line Installation	19
Storage Tank Installation	20
Solar Schematic	21
Controller Installation	23
System Start-up	24
Operating Procedure and Maintenance	25
SEMCO Guarantee	25
SEMCO Collector Drawings	26
Grundfos Circulating Pump	29

## SEMCO SOLAR WATER HEATER INSTALLATION PROCEDURE

The SEMCO solar water heater system is comprised of four subsystems listed as follows:


1. Collector
2. Transport Lines
3. Storage Tank & Pump
4. Controls

Each subsystem should be installed in the sequence listed above.

### COLLECTOR INSTALLATION

The SEMCO solar collector is a complete factory manufactured item that needs no field work other than the assembly and anchoring of the mounting brackets and the bolting of the collector to the brackets. Each set of mounting brackets is factory cut for the particular roof surface on which the collectors are to be mounted.

The first step is to assemble the mounting brackets into their triangular configuration and attach the mounting feet as pictured below.



1 1/2" x 1 1/2" Alum. Angle  
Mounting Bracket

4" x 4" Alum. Angle 4" Long  
Mounting Feet

The assembled mounting brackets are next located on the roof surface where the collectors are to be mounted. The two mounting brackets should be spaced 60 to 72 inches apart depending on the rafter system supporting the roof. When the rafter system and spacings are determined, one of the following four bolting systems should be used.

1. Anchoring may be done with 1/2 in. "J" Bolts where an exposed bolt is not objectionable.
2. Where the ceiling under the mounting roof is exposed decorative beam, drill up thru the beam and roof sheathing and install 1/2 in. carriage or countersunk 1/2 in. machine bolts.
3. Where the ceiling under the mounting roof is finished plaster, locate the rafters through the roof surface, drill 2 - 1/4 in. holes 4 in. deep into the rafter and install 2 - 3/8 in. x 6 in. lag bolts for each mounting foot.
4. Where the collectors are mounted on a truss or frame roof, install a 1/2 in. bolt through the roof sheathing and install a 2 x 4 spreader under the rafter system to distribute the lift across two or more rafters or trusses.

After drilling the bolt holes but before bolting the mounting brackets in place, a pitch pan is nailed in place at each mounting foot location. The mounting brackets are then bolted into place and the pitch pans filled with roofing compound.

Finally the collectors are placed in the mounting brackets and lag bolted together through the predrilled holes provided. When the collectors are moved from the ground to the roof location, care must be taken not to rack the collector frame as it may cause the glass to break.

Tools required for this work are as follows:


1. Hammer
2. Screwdriver
3. Set of socket wrenches and/or end wrenches
4. 3/8 inch power drill & extension cord
5. Set of drills
6. Electric impact wrench (optional)

ORIGINAL PAGE IS  
OF POOR QUALITY

## TRANSPORT LINE INSTALLATION

The transport lines\* are standard soft rolled copper tube with a 3/8 inch O.D. This tube is called 1/4 inch although the I.D. is approximately 5/16 inch. The coil of tube is rolled out and cut to length to run through the attic space from the collectors to the storage tank. Armaflex tube insulation in 6 ft. lengths is slipped over the cut to length tube and each joint secured with duct tape. Leave approximately 3 ft. of uninsulated tube at each end. Drill three 3/8 inch holes through the roof near the collector input and output tubes. Nail a pitch cup in place so the three holes are inside the cup. Push the two transport lines through two of the 3/8 inch holes. Hand bend 1 ft. length of 3/8 inch tube into the shape of a fish hook and install in the third hole. This tube is for the controller sensor wires. Fill the pitch pan with roofing compound. Install cut to length armaflex insulating tube over the exposed transport line tubes. Install the prefabricated sensor well and P/T valve assembly in the collector output tube and attach the transport tube in the fitting provided. Attach the second tube to the collector input tube with the 3/4 inch x 3/8 inch adapter elbow provided. Insulate all exposed copper tube and secure with duct tape. Drill two 3/8 inch holes in ceiling over the storage tank and push the uninsulated ends of the transport lines through the holes. At this time a 1/8 inch hole can be drilled through the ceiling for the collector sensor wire. The installation of the collector sensor wires can be done at this time to save a second trip through the attic. Tools required for this work are the same as for the storage tank installation.

\* Transport line sizes have been increased to 1/2" I.D.





## STORAGE TANK INSTALLATION

The SEMCO solar storage tank is a complete factory manufactured item that is installed like any standard electric water heater plus the two extra copper transport lines for the solar loop to and from the roof. Place the storage tank in its permanent location and make the following pipe hookups:

1. Cold from Street
2. Hot to House
3. P/T Valve
4. Collector input line to tank bottom solar fitting. This line includes the circulating pump and check valve
5. Collector output line to tank top solar fitting. This line includes the thermometer.

See the following solar schematic for a visual description of this work.


The 220 Volt/30 Amp electrical hookup for the booster heater element should be made at this time but left disconnected. This electrical work should be done in accordance with local standard practice and/or local code.

Tools required for this work are as follows:

1. Pipe Cutter
2. Soldering Torch
3. Sandpaper, Solder Flux & Solder




ORIGINAL PAGE IS  
OF POOR QUALITY



Solar Water Heater  
Solar Schematic  
Direct Feed

Solar Engineering & Manufacturing Company



ORIGINAL PAGE IS  
OF POOR QUALITY



Solar Water Heater  
Solar Schematic  
Double Wall Heat Exchanger

## CONTROLLER INSTALLATION

The SEMCO controller is an electronic device that senses the difference in temperature between the collector output temperature and the tank bottom temperature. When the collector temperature is greater than the tank bottom temperature, the controller turns the circulating pump on. The collector sensor has been factory installed in the sensor well and is in place when the sensor well has been installed as described in the installation of the transport lines. The tank sensor has also been factory installed. To install the controller system, place the controller box on the top surface of the storage tank and connect the two pairs of wires from the collector and tank bottom to the terminals marked "coll." and "tank" on the back of the controller box. For geographic locations where direct feed is possible, a freeze sensor is provided in the sensor well. This pair of wires should be connected to the terminal marked "Frez".

The electric cord from the circulating pump is plugged into the outlet provided on the back of the collector box and the collector box is plugged into a 110 Volt/10 Amp electrical outlet. If all the connections have been made correctly, the circulating pump will start. Quickly unplug it because the pump can be damaged if allowed to run dry for any length of time.

### SYSTEM START-UP

Having completed the installation of the four subsystems the complete system is now ready for start up. For the direct feed system, first, open the cold water cut-off valve and fill the storage tank with water and check for leaks. Next, open the P/T Valve on top of the collector and bleed off all air and again check for leaks.

The system is now ready to start up. Plug the controller into the 120 Volt outlet. The circulating pump will move cold water from the bottom of the tank into the solar collectors where it will be heated. The hot water will flow down into the top of the storage tank. The thermometer will register the temperature of the collector output water.

For the double wall heat exchanger solar tanks, the start-up procedure is to first fill the storage tank with water and check for leaks. Next, fill the solar circulating loop with the anti-freeze liquid provided by removing the P/T Valve on top of the collector and pouring the liquid into the system. All air should be bled from the solar loop and the P/T Valve replaced. The startup procedure is the same as described above for the direct feed system.

Finally, plug the electric booster into the 220 volt outlet.



#### OPERATING PROCEDURE AND MAINTENANCE

After completing the start-up procedure, the system will operate automatically for years with no adjustments or maintenance required.

The only possible malfunction that could cause the system not to operate correctly, would be air trapped in the circulating loop of the double wall heat exchanger system. If the thermometer shows no hot water flowing from the collector to the storage tank, remove the collector P/T Valve again and add more anti-freeze liquid to replace the entrapped air.

#### SEMCO GUARANTEE

The SEMCO Solar Water Heater is guaranteed for five (5) years against defects in material and workmanship under normal operating conditions. Should the controller or pump malfunction within five (5) years of the date of installation, return the defective part to the SEMCO plant for repair or replacement.




## FLAT PLATE SOLAR COLLECTOR

The Semco flat plate solar collector is designed to absorb and trap direct and diffused solar radiation. The absorbed energy is transferred by conduction and convection to the collector tubing which heats water circulating through the collector. This heated water can be used to supply residential and commercial needs for hot water. The collectors can also be used to heat swimming pool water and supply the hot water requirements for space heating and cooling.


The collector plate is constructed of  $\frac{3}{4}$  inch copper tubing on 6 inch centers soldered to a grooved copper plate. The surface facing the sun is painted with a flat black industrial enamel.

The collector box is constructed of aluminum and insulated with polyurethane. The glazing is standard double strength window glass\* with aluminum mullions and frame.

## SOLAR WATER HEATER



10 Feet Long  
4 Feet Wide  
4 Inch Thick




\* plate glass changed to tempered glass


Solar Engineering & Manufacturing Company

ORIGINAL PAGE IS  
OF POOR QUALITY

# Liquid Flat Plate Solar Collector Section -- Full Size






\* plate glass changed to tempered glass



NASA Contract - NAS8-32248  
Date -- March 23, 1977  
Drawn By -- D. B. Aspinwall

**Liquid Flat Plate Solar Collector**  
Box Details -- 1/2" = 1'-0"



Material - Aluminum - 606-T6  
 Aluminum Box - 1/8" x 2" x 4" side angle - 0.020 Alum. Bottom  
 \*Glazing - Double - 1/8" DBS Glass - 5 pcs. 24" x 48"  
 Insulation - 1" Technifoam - TF-400 - R=9  
 Absorber Plate - 3/4 Copper Tube finned with 0.010 Sheet Copper  
 Absorber Surface - Non-selective flat black enamel  
 Tube Configuration - Serpentine

\* plate glass changed to tempered glass




NASA Contract - NAS8-32248  
 Date -- March 23, 1977  
 Drawn By -- D. B. Aspinwall



ORIGINAL PAGE IS  
OF POOR QUALITY

- A. Terminal Box
- B. Switch
- C. O-rings
- D. Rotor Can
- E. Top Bearing
- F. Stator
- G. Gasket
- H. Bearing Plate
- I. Flow Adjustment Arm
- J. Variable Flow Adjustment Plate
- K. Impeller
- L. Bottom Bearing
- M. Thrust Bearing
- N. Pump Chamber
- O. Stator Housing
- P. Rotor
- Q. Winding Protection
- R. Shaft
- S. Plug/Indicator



### INFORMATION: Two-speed circulator pump — UPS 20-42

The UPS 20-42 is fitted with a variable flow control and also features a two-speed motor. The head is controlled by the flow adjustment arm (I) and the choice of speed is made by hand on the switch (B) or made automatically in conjunction with remote control.

### CONSTRUCTION

The UPS 20-42 is a water lubricated pump. However, in order to protect the rotor (P) and bearings (E,L) from damaging impurities which may be present in the circulating water, they are separated from the stator (F) and the pump chamber by a liquid filled rotor can (D). The motor shaft (R) extends out from the rotor can, into the pump chamber through the aluminum oxide bearing (L), which also functions as a seal. During initial operation, the pump is automatically self-vented; however, due to the isostatic principle, there is no further recirculation of water into the closed rotor can. The pump's "diamond-hard" aluminum oxide bearing construction, combined with the high starting torque of the motor, ensures re-start after shutdown.

### MATERIALS

<b>Stainless steel:</b> .....	Rotor can, shaft, rotor cladding, bearing plate, impeller, variable flow adjustment plate, thrust bearing cover.
<b>Aluminum oxide:</b> .....	Top bearing, shaft ends, bottom bearing.
<b>Aluminum:</b> .....	Stator housing.
<b>Carbon/aluminum oxide:</b> .....	Thrust bearing.
<b>Cast iron:</b> .....	Pump housing.
<b>Ethylene/propylene rubber:</b> .....	O-rings, gasket.
<b>Silicone rubber:</b> .....	Winding Protection.

### APPLICATIONS

The UPS 20-42 should only be used in closed systems (i.e. solar, hydronic) for the circulation of water. However, solutions such as ethylene glycol can be used without hindering pump performance. For open systems, order the Grundfos model UP 25-42 SF which has an all stainless steel pump housing.

